

Camp Edgewood Road

Section 1

Begin Cold Planing	STA 20+00
End Cold Planing	STA 85+45
Average Thickness of Cold Planing	2 in.
Width of Cold Planing	18 ft.
Quantity of Cold Planing required	13,090 s.y.
Begin Cement Treatment	STA 20+00
End Cement Treatment	STA 85+45
Width of Cement Treatment	19 ft.
Quantity of Cement Treatment req.	13,817 s.y.
Begin 2" of Stone	STA 20+00
End 2" of Stone	STA 85+45
Width of Stone Placement	19 ft.
Quantity of Stone required	1,121 Tons
Begin 8 ½" Soil Cement	STA 20+00
End 8 ½" Soil Cement	STA 85+45
Width of Soil Cement	19 ft.
Quantity of Soil Cement required	13,817 s.y.
Begin 2" Asphalt	STA 20+00
End 2" Asphalt	STA 85+45